

SECTION 02989

MISCELLANEOUS WORK AND CLEANING UP

PART 1.00 - GENERAL

1.01 DESCRIPTION

A. Work Included:

Furnish all labor, materials, equipment and incidentals required to do all miscellaneous work and cleaning up not otherwise specified. The work of this Section includes, but is not limited, to the following:

1. Driveways shall be made accessible at the end of each work day. Any extra work required to accomplish this shall be included in this item.
2. Provide access for mail delivery on a daily basis.
3. Provide access for trash pickup. CITY shall provide pickup schedule so that work does not conflict with trash vehicles.
4. Restoration, repair or replacement of existing catch basins, sewer manholes, sewer and drainage pipe, water and sewer services encountered during construction.
5. Restoration of concrete walks, driveways, fences, walls, mailboxes, signs, etc., as required.
6. Installation of erosion control measures and continued maintenance for the duration of the Contract.
7. Restore grass areas with loam and seed.
8. Cleaning up the construction site.
9. Providing and setting up of temporary Fluorescent Traffic Cones (RIDOT Std. 26.1.0) and or Polyethylene Drums with markings around the work zones during construction operations and overnight.
10. Maintaining the safe passage of traffic in accordance with specified traffic control.
11. All water gate boxes shall be cleaned out using a vacuum and a key shall be placed on the valve nut in the presence of Water Utilities Supervisors to assure proper cleaning has taken place. Failure to do so will delay in final payment.
12. All other work incidental to completing the project.

PART 2.00 - PRODUCTS

None this Section

PART 3.00 - EXECUTION

3.01 CLEAN UP

- A. The Contractor shall remove all construction material, excess excavation, equipment or other debris remaining on the job as a result of construction operations and shall render the site of the work in a neat and orderly condition at least equal to that which existed prior to the start of construction.

- B. The Contractor shall remove all material from the water gate boxes with the use of an appropriate vacuum. The Contractor shall install a key on the valve nut in the presence of a Water Utilities Supervisor to assure the box has been cleaned appropriately. Failure to do so will result in delay of payment.

END OF SECTION