

SECTION 02989

MISCELLANEOUS WORK AND CLEAN UP

PART 1.00 – GENERAL

1.01 DESCRIPTION

A. Work Included:

Furnish all labor, materials, equipment and incidentals required to do all miscellaneous work and cleaning up not otherwise specified. The work of this Section includes, but is not limited, to the following:

1. Installation of the ten-foot high chain link fence, fabric, rails, gates, etc., including any demolition work if the City decides to choose add/alt item 1.
2. Cleaning up the construction site.
3. All other work incidental to completing the project.

PART 2.00 – PRODUCTS

None this Section

PART 3.00 – EXECUTION

3.01 CLEAN UP

- A. The Contractor shall remove all construction material, excess excavation, equipment or other debris remaining on the job as a result of construction operations and shall render the site of the work in a neat and orderly condition at least equal to that which existed prior to the start of construction

END OF SECTION